

Lead Testing

Remediation Plan

Pursuant to the Commissioner of Health,
Public Health Law Sections pertaining to the
Official Compilation of Codes, Rules and Regulations
of the State of New York for all School Districts
shall perform remediation services
to units that exceed the regulated thresholds
by means of:

1. Take off line or shut off the affected unit.
2. Clean any residue or corrosion that could sway the test.
3. Retest unit.
4. To retest: Run water for 5-10 minutes, Let it stand 8-18 hours,
Then do a first draw.
5. If the test still comes back positive: Replace unit, Run water for
15 minutes, Retest unit.
6. Final effort: Replace the water line if needed.